

PROJECT FILE

CROKE PARK / DUBLIN



Following the success of phase 2 , the main contractors requested that more ALPS Suspended Access Platforms be incorporated into the roof access solution:

A large Alloy Space Frame Platform was initially assembled and installed; this platform was 17.08M X 14.64M and equipped with on board hoists.

A smaller 17M x 2.5M platform was also erected to access the large gutters ahead of the main platform.



The main working platform was "fed" using a 16M X 1.22M power operated Suspended Access Platform powered by two 2Te man-riding hoists, raising and lowering the platform and its 1000Kg payload to and from the main platform at a variable speed of up to 18mpm.

ALPS erected a fourth platform to access the corner of the roof & accelerate the program in time for the start of the Hurling season. (Gaelic games)

ALPS & their Industrial Abseiling Team erected and managed the entire Suspended Access System for this project.



www.alps-uk.com

Access Lifting Pulling & Safety Ltd PO Box 896 Sheffield S17 4YN

Tel: 01246 413111 email: access@alps-uk.com